

ADDENDUM NO. 1

PROJECT: Arkansas Northeastern College
New Center for Allied Technologies
Blytheville, Arkansas

DATE: March 2, 2017

PROJECT BID DATE: Wednesday, March 15, 2017 at 2:00 PM, Central Time

ARCHITECT: A. C. Williams, Architect
601 Shadow Ridge Drive
Jonesboro, AR 72404
Phone/Fax: 870-935-2852
Email: acwilliamsarchitect@suddenlink.net

All bidders shall take notice of the following listed revisions and/or additions to the drawings and/or specifications for the above referenced project and adjust their bid accordingly. The revisions and corrections are hereby made a part of said documents and subsequent construction as if therein included.

It is the responsibility of General Contractors to verify that submitted bids include any and all adjustments required by addendums.

Products/Manufacturers listed below as acceptable “equal” are not relieved from meeting all physical, performance and/or detail characteristics of products specified. Failure to do so will be justification for rejection.

The following items refer to the Construction Drawings and/or Specifications:

- Item 1. Pre-Bid Meeting:**
A Pre-Bid Meeting is scheduled for Wednesday, March 8, 2017 at 1:00 P.M. Central Time in Room A101, 1st floor of the John P. Sullins Administration Building on the main campus of Arkansas Northeastern College, 2501 South Division Street (Highway 61), Blytheville, AR 72415. This meeting is not mandatory but General Contractors and Subcontractors are encouraged to attend.
- Item 2. Section 02316 – Fill and Back Fill:**
Delete references to 98% modified proctor and replace with 98% standard proctor to match structural drawing requirements and recommendations per soils report.
- Item 3. Sections 08411 – Aluminum-Framed Storefronts and 08441 – Glazed Aluminum Curtain Walls:**
Glazed Aluminum-Framed Storefront System YKK-AP-YWW-45-FS (front glazed) and Glazed Aluminum Curtain Wall System YKK-AP-YCW-750-OG (front glazed) as manufactured by YKK North America Group, 1850 Parkway

Place SE, Suite 300, Marietta, GA 30067, USA are approved as acceptable equals subject to note above.

Item 4. Section 09680 - Carpet:

Change all references of 12" x 24" carpet to 12" x 48" carpet. Carpet is to have standard "Prefix" adhesive for installation. Delete all references to any other kinds of adhesive.

Item 5. Drawing Sheets C6, C9 and C16:

Delete Civil Sheets C6, C9, C16 dated 12/15/2016. Replace with the following attached Civil Sheets C6, C9, C16 with Revised Date 03/01/2017.

C6 – Structure table now includes drainage inlets north of the Sun Room.

C9 – Sanitary sewer invert elevations lowered a few tenths of a foot.

C16 – Civil indexing sheet is included to show an overall view of the site work.

Item 6. Drawing Sheets E2, E3 and E21:

Refer to Sheets E2 – Enlarged Floor Plan Area A – Lighting and E3 – Enlarged Floor Plan Area B – Lighting.

- Change three (3) "L22" fixtures in Corridor 225 outside Men 216 and Women 223 to "L11" fixtures.

- Change three (3) "L22" fixtures in Corridor 102 outside Men 122 and Women 123 to "L11" fixtures.

Refer to Sheet E-21 – Lighting Fixture Schedule. "L11" fixture to be H-15116-96/1/2"CB(length to be determined)-96/WGR-96/31W, LED2, 3000K, Non Dimming, BCM-277V as manufactured by Hi-Lite Manufacturing Company.

END OF ADDENDUM NO. 1
TOTAL WITH ATTACHMENTS 5 PAGES