andrew hicks | architect

209 North Pierce Little Rock Arkansas, 72205 www.andrewhicksarchitect.com

voice 501.219.1614 fax 501.219.1613

Andrew Hicks: Project Manager

Phone: (501) 219-1614 FAX: (501)219-1613

andrew@andrewhicksarchitect.com

Re: A K-4 CLASSROOM ADDITION BUILDING

Owner: SLOAN HENDRIX SCHOOL DISTRICT/ IMBODEN, AR

Superintendent of Schools

Mr. Clifford Rorex

Highway 115 / Greyhound Circle / PO Box 1080,

Imboden, Arkansas 72434

Project to be located on:

Sloan Hendrix School Campus, Imboden, Arkansas 72434

ADDENDUM #4

April 25, 2017

Modifications or clarifications to original plans and specifications:

CONCRETE SLAB

- 1. 4" of washed rock shall be required under all building slabs. Disregard any reference to other types or thickness of drainage fill.
- 2. Contractors shall disregard any reference in the documents to under slab insulation. No insulation is required under the building slab

EXTERIOR WALLS.

3. The original plans documents call for 3" of vinyl faced insulation to be provided inside the metal exterior wall panels. The contractor shall disregard this requirement. NO insulation shall be required between the exterior metal siding panels and the exterior sheathing. The only insulation required in the exterior walls is the insulation between the exterior studs.

ELECTRICAL

4. The Intercom System has been removed from the project in a previous addendum. However, for future use by others, the contractor shall be required to mount electrical boxes at any Intercom device shown on the plans to be mounted in or on a wall. Provide conduit from box to above ceiling. NO boxes are required at ceiling mounted devices.

END OF ADDENDUM #4