

ADDENDUM NO.3  
TO  
PLANS AND SPECIFICATIONS  
FOR  
INDEPENDENCE COUNTY SENIOR CITIZENS CENTER  
BATESVILLE, ARKANSAS  
M-N 22-010  
May 5, 2023

The following revisions shall be made to the plans and specifications and become a part thereof:

1. On the plans and kitchen equipment schedule the K-08 should be K-11 (blast chiller) which is to be relocated from the existing center.
2. The Howe casing in detail J-01/A-401 is to be used at the exterior windows and any wood door opening.
3. All forms provided with the bid packet shall be completed and submitted in the envelope provided.
4. The bid opening time shall remain at 11:00 A.M. on May 9, 2023.
5. In order to satisfy Health Department guidelines for food preparation surfaces to be non-absorbent and easily cleaned, ceramic tile has been selected as the finish on the kitchen walls. The finish schedule on Sheet A-601 calls for full height on all walls in the janitor/housekeeping/kitchen staff toilet, kitchen and dishwashing. The ceiling heights are shown on same schedule.
6. Provide stoop to exterior door 27 (mechanical room 125) and provide 6' wide sidewalk to walk on north side of building.
7. The condensing units are to be located near the mechanical rooms as space permits. See sheets E-201 and E-202 for locations. Note that a grease trap is located near units C-4, C-5, C-6, and C-7.

8. The three compartment sink K-61 listed in the specifications to be relocated is to remain at its present location. The Contractor shall provide and install a three compartment sink equal to Regency 72-1/2" 16 gauge stainless steel three compartment commercial sink with one drainboard. Sink to be plumbed with drain and supply lines and three sets of faucets. Attachments as shown in kitchen fixture schedule to be attached to sink with required electrical.

(End of Addendum)

MILLER-NEWELL ENGINEERS, INC.  
P.O. Box 705  
510 Third Street  
Newport, AR 72112