

**SECTION 00 9111
ADDENDUM NUMBER 2**

PARTICULARS

1.01 DATE: JULY 01, 2025

1.02 PROJECT: BRTC POCAHONTAS - OLD WELDING SHOP RENOVATIONS

1.03 PROJECT NUMBER: 2503

1.04 OWNER: BLACK RIVER TECHNICAL COLLEGE

1.05 ARCHITECT: STEILING ARCHITECTURE

TO: PROSPECTIVE BIDDERS

2.01 THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND MODIFIES THE BIDDING DOCUMENTS DATED JUNE 12, 2025, AND ADDENDUM NUMBER 1 ISSUED JUNE 30, 2025, WITH AMENDMENTS AND ADDITIONS NOTED BELOW.

2.02 ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED IN THE BID FORM. FAILURE TO DO SO MAY DISQUALIFY THE BIDDER.

2.03 THIS ADDENDUM CONSISTS OF 1 PAGE.

CHANGES TO THE PROJECT MANUAL

3.01 SECTION 07 4213 - METAL WALL PANELS

A. 2.02 MANUFACTURED METAL PANELS

1. Item C. Interior Liner Panel, Items 1 and 3:
 - a. Profile shall be standard PBR vertical panel.
 - b. Panel width shall be 36" in lieu of 12" shown.

CHANGES TO THE DRAWINGS

4.01 DRAWING A401 - ARCHITECTURAL DETAILS

A. DETAIL #5 - Exterior Wall Detail - Typical

1. Omit reference to Interior Liner Panel "Remains". Provide new interior liner panel.

CLARIFICATIONS

5.01 QUESTIONS ABOUT ITEMS ON THE DRAWINGS:

A. Are interior liner panels new?

1. Yes. Interior liner panels shall be 36" wide, 24 gauge, PBR liner panels installed vertically on PEMB wall girt system over Simple Saver Insulation system.

END OF SECTION